

Tele (Civ) : 0135-2970278
Tele (Mil) : 2282
e-mail : apscllementtown@gmail.com

Army Public School
Clement Town,
Dehradun (UK)-248002

1001/APSCT /

02 Jan 2026



(Name of firms)

CALL FOR QUOTATION

Dear Sir / Madam,

1. This School intends to renovat/ maintenance of Girls washrooms (T1 & T5) of Primary Wing at ground floor of APS Clement Town, Dehradun as per details given below:-

Ser No	Details of Items	A/U	Qty	Rate	Remarks
(a)	Renovatio/maintenance of Girls Washrooms T-1 & T-5 of Primary Wing at Ground Floor of APS Clement Town	Nos	02		

2. Scope of work for the above mentioned job is enclosed.

3. You are requested to intimate your rate for above mentioned work so as to reach this office by 10 Jan 2026 at 1100 hrs in a sealed envelope along with scope work / specification duly signed and affixed with the office stamp. Quotation received thereafter will not be accepted. No intimation will be given regarding acceptance and rejections.

4. The quotations to be given only on the letter head bearing the name of Firm with GST No alongwith scope of work /specification. Quotations and technical specification should be signed by the head of firms and vendors duly affixed with the office stamp.

5. Firm/vendor for supply of stores will be decided by the School Purchase Committee/Board of Officers based on lowest rates and quality of stores being provided by them.


6. Guarantee and warranty of the stores for stipulated time frame will also be strictly adhered to.

7. Only appropriate charges of GST and service charges, if any will be accepted.

8. Stores so demanded to be provided/supplied by Firm/vendor in School office and no extra charges on account of transportation will be added later on.

Thanking you,

Yours sincerely


(Bhavna Bhargava)
Principal


HC

Enclosures: As above.

**SPECIFICATION /SCOPE OF WORK FOR RENOVATION GIRLS WASHROOMS T-1 & T-5 OF
PRIMARY WING OF APS CLEMENT TOWN**

Ser No	Specification / Scope of Work	A/U	Qty	Rate	Amount
Girls Washroom: T-1 Primary Wing					
1.	Providing and laying vitrified floor and wall tiles (including dismantling old tiles) in different sizes (450mm x 300mm, 300mm x 200mm and 300 x 300mm) with water absorption less than 0.08% and conforming to S: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement: 4 coarse sand), jointing with grey cement slurry. ✓	Sqft	1100		
2.	Repairs to plaster of thickness 12mm to 20mm in patches of area 2.5 sq meters and under, including cutting the patch in proper shape with cement mortar 1:4 (1 cement : 4 fine sand) ✓	Sqft	1050		
3.	Distempering with 1 st quality acrylic distemper and white cement based putty of approved make (new work 2 coat) ✓	Sqft	1050		
4.	MS Door frame 100mm x 60mm ✓	Nos	04		
5.	35mm thick 6ft x 2.5 ft factory made solid panel PVC door shutter of single piece ✓	Sqft	03		
6.	Providing & fixing glass panes with putty in windows, clerestory windows, all complete with 4.0mm thick glass panes ✓	Sqft	52		
7.	Cleaning of choked sewer line and laying new line with PVC 100mm pipe including all fitting excluding WC ✓	Rft	35		
8.	Providing and applying damp guard in walls and finishing wall with matching shade. ✓	Sqft	120		
9.	Oval shape counter washbasin including tap and waste pipe ✓	Nos	03		
Total		-	-		
Girls Washroom: T-5 Primary Wing					
1.	Providing and laying vitrified floor and wall tiles (including dismantling old tiles) in different sizes (450mm x 300mm, 300mm x 200mm and 300 x 300mm) with water absorption less than 0.08% and conforming to S: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement: 4 coarse sand), jointing with grey cement slurry. ✓	Sqft	1100		
2.	Repairs to plaster of thickness 12mm to 20mm in patches of area 2.5 sq meters and under, including cutting the patch in proper shape with cement mortar 1:4 (1 cement : 4 fine sand) ✓	Sqft	1050		
3.	Distempering with 1 st quality acrylic distemper and white cement based putty of approved make (new work 2 coat) ✓	Sqft	1050		
4.	MS Door frame 100mm x 60mm ✓	Nos	04		
5.	35mm thick 6ft x 2.5 ft factory made solid panel PVC door shutter of single piece ✓	Sqft	03		
6.	Providing & fixing glass panes with putty in windows, clerestory windows, all complete with 4.0mm thick glass panes ✓	Sqft	52		
7.	Cleaning of choked sewer line and laying new line with PVC 100mm pipe including all fitting excluding WC ✓	Rft	35		
8.	Providing and applying damp guard in walls and finishing wall with matching shade. ✓	Sqft	120		
9.	Oval shape counter washbasin including tap and waste pipe ✓	Nos	03		
Total		-	-		
G/Total					



Chakr