

Tele (Civ) : 0135-2970278  
Tele (Mil) : 2282  
e-mail : [apscllementtown@gmail.com](mailto:apscllementtown@gmail.com)



Army Public School  
Clement Town,  
Dehradun (UK)-248002

1001/APSCT /

16 Jan 2026

(Name of firms)

**CALL FOR QUOTATION**

Dear Sir / Madam,

1. This School intends to install / fix of angle iron caging around all overhead water tanks of the school building of APS Clement Town, Dehradun as per details given below:-

Ser No	Details of Items	A/U	Qty	Rate	Remarks
(a)	Installation Iron frames cage around all overhead water tanks of the school building to protect monkeys menace with 6' x 6' door with locking system.(Size: Length- 20ft, Width -15ft and Height - 8ft above platform) <b>Specification:</b> Mild Steel Angle section of Size - 35 x 35mm, joints mitered and welded by angle iron 35 x 35 x 5 mm and covered by 1inch square MS mesh. Painting : Premier and black paint <b>Material:</b> Angle iron-280Kg, MS Mesh:1" 800sqft , Enamel Paint Black 2 Coat - 920 sqft	Nos	04		

2. Scope of work for the above mentioned job is enclosed at Appendix.

3. You are requested to intimate your rate for above mentioned work so as to reach this office by 27 Jan 2026 at 1100 hrs in a sealed envelope along with scope work / specification duly signed and affixed with the office stamp. Quotation received thereafter will not be accepted. No intimation will be given regarding acceptance and rejections.

4. The quotations to be given only on the letter head bearing the name of Firm with GST No alongwith scope of work /specification. Quotations and technical specification should be signed by the head of firms and vendors duly affixed with the office stamp.

5. Firm/vendor for supply of stores will be decided by the School Purchase Committee/Board of Officers based on lowest rates and quality of stores being provided by them.

6. Guarantee and warranty of the stores for stipulated time frame will also be strictly adhered to.

7. Only appropriate charges of GST and service charges, if any will be accepted.

8. Stores so demanded to be provided/supplied by Firm/vendor in School office and no extra charges on account of transportation will be added later on.

Thanking you,

Yours sincerely

*Bhargava*  
(Bhavna Bhargava)  
Principal

**Enclosures:** As above.

**Appendix**

(Refer to Para 2 of APS Clement Town letter No 1001/APSCT dated 16 Jan 2026)

**SPECIFICATION /SCOPE OF WORK FOR INSTALLATION/ FIXING IRON CAGING  
AROUND ALL OVERHEAD WATER TANKS OF THE SCHOOL BUILDING  
OF APS CLEMENT TOWN**

Ser No	Specification / Scope of Work	A/U	Qty	Rate	Amount
1	<p><b><u>Providing and fixing angle iron frame cage for protection of water tanks from monkeys</u></b></p> <p>(a) Providing and fixing monkey-protection cage constructed with mild steel angle iron framework using angle sections of size <b>35×35×5 mm</b>, including cutting, jointing, mitring and welding at all joints, complete in all respects. All Iron angles of the frame to be fixed/ grouted on the platform through concrete material upto height of 1ft. The cage shall be covered with <b>1 inch square MS welded mesh</b>, properly fixed to the angle iron frame with MS flats/welded supports, ensuring rigidity and durability. The work includes providing <b>one access opening of size 6 ft × 6 ft</b> with MS framed and 4 ft high 2.5 ft wide <b>MS Ladder</b> and door arrangement for maintenance purposes. The entire structure shall be finished with <b>two coats of black enamel paint over a suitable primer</b>, including surface preparation, cleaning, and making good the area after completion of work, complete as directed by the School Management.</p> <p>(b) Misc work - As per site and management requirement.</p> <p>(c) <b>Size of Enclosure :-</b> <b>Length:</b> 20 ft <b>Width:</b> 15 ft <b>Height:</b> 8 ft (above existing platform)</p> <p><b>Material:</b> Angle iron-280Kg, MS Mesh:1" 800sqft Enamel Paint Black 2 Coat – 920 sqft for each.</p>	Nos	04		

